

NAVAL POSTGRADUATE SCHOOL

Monterey, California



THESIS

**USE OF PRINCIPAL COMPONENT ANALYSIS FOR
THE IDENTIFICATION AND MAPPING OF PHASES
FROM ENERGY-DISPERSIVE X-RAY SPECTRA**

by

Daniel J. Chisholm

March 1999

Thesis Advisor:

Alan G. Fox

Approved for public release; distribution is unlimited.

DTIC QUALITY INSPECTED 2

19990205 033

REPORT DOCUMENTATION PAGE			Form Approved OMB No. 0704-0188	
Public reporting burden for this collection of information is estimated to average 1 hour per response, including the time for reviewing instruction, searching existing data sources, gathering and maintaining the data needed, and completing and reviewing the collection of information. Send comments regarding this burden estimate or any other aspect of this collection of information, including suggestions for reducing this burden, to Washington Headquarters Services, Directorate for Information Operations and Reports, 1215 Jefferson Davis Highway, Suite 1204, Arlington, VA 22202-4302, and to the Office of Management and Budget, Paperwork Reduction Project (0704-0188) Washington DC 20503.				
1. AGENCY USE ONLY (Leave blank)	2. REPORT DATE March 1999	3. REPORT TYPE AND DATES COVERED Master's Thesis		
4. TITLE AND SUBTITLE USE OF PRINCIPAL COMPONENT ANALYSIS FOR THE IDENTIFICATION AND MAPPING OF PHASES FROM ENERGY- DISPERSIVE X-RAY SPECTRA		5. FUNDING NUMBERS		
6. AUTHOR(S) Chisholm, Daniel J.				
7. PERFORMING ORGANIZATION NAME(S) AND ADDRESS(ES) Naval Postgraduate School Monterey CA 93943-5000		8. PERFORMING ORGANIZATION REPORT NUMBER		
9. SPONSORING/MONITORING AGENCY NAME(S) AND ADDRESS(ES)		10. SPONSORING/MONITORING AGENCY REPORT NUMBER		
11. SUPPLEMENTARY NOTES. The views expressed in this thesis are those of the author and do not reflect the official policy or position of the Department of Defense or the U.S. Government.				
12a. DISTRIBUTION/AVAILABILITY STATEMENT Approved for public release; distribution is unlimited.		12b. DISTRIBUTION CODE		
13. ABSTRACT (maximum 200 words) Multivariate statistical analysis methods such as Principal Component Analysis (PCA) are now finding applications in electron microscopy including the analysis of energy dispersive x-ray spectra (EDS). The aim in this thesis is to extend EDS beyond its conventional use in the measurement of elemental distributions to allow both the identification of chemical phases and the mapping of their distribution. In the present work, PCA was applied to the analysis of modeled spectra representing interfaces where diffusion and/or an interface reaction had occurred. A search routine was developed to find physically possible interface phases using the principal components found by PCA. From the modeled data, it was shown that an interface phase could, in principle, be found using PCA but that it is embedded in a cluster of physically possible spectra. The technique was then applied to experimental data obtained from an interface between chemically vapor deposited diamond (CVDD) and Cr ₂ O ₃ . The results followed the same pattern as was seen with the modeled data. Criteria for experimental EDS spectra other than those used to define a physically meaningful spectrum are discussed. These should help further limit the cluster of possible answers found allowing a correct determination of the real interface phase.				
14. SUBJECT TERMS Multivariate Statistical Analysis, Principal Component Analysis, Energy Dispersive X-ray Spectra			15. NUMBER OF PAGES 104	
			16. PRICE CODE	
17. SECURITY CLASSIFICATION OF REPORT Unclassified	18. SECURITY CLASSIFICATION OF THIS PAGE Unclassified	19. SECURITY CLASSIFICATION OF ABSTRACT Unclassified	20. LIMITATION OF ABSTRACT UL	

Approved for public release; distribution is unlimited

**USE OF PRINCIPAL COMPONENT ANALYSIS FOR THE
IDENTIFICATION AND MAPPING OF PHASES FROM
ENERGY-DISPERSIVE X-RAY SPECTRA**

Daniel J. Chisholm
Lieutenant, United States Navy
B.S., Rensselaer Polytechnic Institute, 1990


Submitted in partial fulfillment of the
Requirements for the degree of

MASTER OF SCIENCE IN MECHANICAL ENGINEERING


from the


**NAVAL POSTGRADUATE SCHOOL
March 1999**

Author: _____


Daniel J. Chisholm

Approved by: _____


Alan G. Fox, Thesis Advisor


Terry R. McNelley, Chairman
Department of Mechanical Engineering

ABSTRACT

Multivariate statistical analysis methods such as Principal Component Analysis (PCA) are now finding applications in electron microscopy including the analysis of energy dispersive x-ray spectra (EDS). The aim in this thesis is to extend EDS beyond its conventional use in the measurement of elemental distributions to allow both the identification of chemical phases and the mapping of their distribution.

In the present work, PCA was applied to the analysis of modeled spectra representing interfaces where diffusion and/or an interface reaction had occurred. A search routine was developed to find physically possible interface phases using the principal components found by PCA. From the modeled data, it was shown that an interface phase could, in principle, be found using PCA but that it is embedded in a cluster of physically possible spectra. The technique was then applied to experimental data obtained from an interface between chemically vapor deposited diamond (CVDD) and Cr_2O_3 . The results followed the same pattern as was seen with the modeled data. Criteria for experimental EDS spectra other than those used to define a physically meaningful spectrum are discussed. These should help further limit the cluster of possible answers found allowing a correct determination of the real interface phase.

TABLE OF CONTENTS

I. INTRODUCTION.....	1
II. BACKGROUND.....	3
A. THE TRANSMISSION ELECTRON MICROSCOPE	3
B. ENERGY-DISPERSIVE X-RAY (EDS) ANALYSIS.....	5
C. PRINCIPAL COMPONENT ANALYSIS (PCA)	10
D. PCA OF TEM SPECTRAL DATA.....	13
III. MODELED DATA SETS OF KNOWN COMPOSITION.....	17
A. PCA AND CHANGE OF BASIS.....	17
B. ORTHOGONAL DATA SETS.....	20
C. NON-ORTHOGONAL DATA SETS	33
D. NORMALIZATION TECHNIQUES.....	45
IV. MODELED DATA SETS OF UNKNOWN COMPOSITION.....	49
A. SEARCH ROUTINE AND PHYSICAL SPACE CRITERIA	49
B. ORTHOGONAL TEST	52
C. NON-ORTHOGONAL TESTS	54
V. EXPERIMENTAL DATA.....	67
A. DATA SET BACKGROUND AND PREPARATION.....	67
B. EXPERIMENTAL DATA TESTS.....	71
VI. SUMMARY AND CONCLUSIONS.....	87
LIST OF REFERENCES	91
INITIAL DISTRIBUTION LIST	93

ACKNOWLEDGEMENT

I would like to express my gratitude and appreciation to my thesis advisor Dr. Alan G. Fox and my co-thesis advisor Dr. Martin Saunders, who has since accepted a position at Uppsala University, for their counsel and guidance.

Special thanks are also due to Dr. S. Menon and Mr. Rich Hashimoto for the invaluable laboratory assistance and the very helpful input on this topic that they provided.

I. INTRODUCTION

Energy dispersive x-ray spectroscopy (EDS) has been used for many years in the transmission electron microscope (TEM) to find the elemental composition of a sample. Over the years, the analysis has been refined to produce truly quantitative results. Unfortunately, where the sample consists of a diffuse mixture of phases, this data has not always been able to provide phase information, i.e. the technique cannot always determine what phases are present and their distribution in the sample. An EDS spectrum, by itself, does not give the information necessary to determine the phases present in a multi-phase sample. The work presented in this thesis is an attempt to develop a technique which can determine the phase composition and distribution of a sample through the use of a series of EDS spectra and one form of Multivariate Statistical Analysis (MSA), Principal Component Analysis (PCA).

If a data set consists of n observations of p variables then this data, an $n \times p$ matrix, can be thought of as n points in p dimensional space. By analyzing the data using PCA another set of axes, called principal component axes, which are combinations of the original p variables, is found that these also describe the n observations. PCA is known as a linear reduction technique because, although there are p principal components generated, if the data set was highly correlated then most of the information that was contained in the original data is now contained in q principal components where $q \ll p$. Thus, there is a reduction in the number of axes or principal components that are necessary to describe the data set, or at least to describe the majority of the information contained in the data set.

The orthogonal basis and concentration of information provided by PCA is used to help reconstruct the phase composition of the sample. The analysis presented here considers two types of data, modeled and experimental. Using modeled data, the correct answer, i.e. the makeup and distribution of the phases, was known ahead of time. This allowed the development of a technique to recover the phase information and an understanding of the behavior of that technique under different conditions. It also allowed small changes to be inserted into the data to see their effect on the analysis.

The first applications of this technique to actual experimental data are then discussed. The analysis of real data requires the introduction of additional pre-processing steps to remove the Bremsstrahlung background and to reduce the data into a manageable form. The analysis of a diffuse interface between chemical vapor deposited diamond (CVDD) and chromium oxide is considered. This is expected to have a similar form to the modeled test data used to develop the phase analysis technique. The initial results of the analysis are presented and recommendations for further studies are given.

II. BACKGROUND

A. TRANSMISSION ELECTRON MICROSCOPE (TEM)

The benefit of using a microscope with an electron beam as the source of illumination is due to the much shorter wavelength of electrons compared to visible light. The minimum resolvable distance of any microscope is directly related to the wavelength of the illuminating wave; the electron has a much smaller wavelength than visible light so its minimum resolvable distance is much smaller. Unfortunately, the poor quality of the lenses in a TEM do not allow the theoretical resolution to be reached because of lens aberrations, but resolutions of the order of 0.2 nm in images are easily possible. A brief description of the TEM and the information available from it is provided below. [Ref. 1]

An electron gun emits electrons either by thermionic or field emission depending on the type of emitter installed. The lenses, consisting of the first and second condenser lenses and the prefield of the objective lens, focus the electron beam onto the sample. A schematic of a TEM is shown in Figure 2.1. Some of the electrons travel straight through the sample or are absorbed neither of which produce useful information. Others, however, are scattered either elastically or inelastically. These electrons as well as the other signals produced by the incident beam, such as x-rays and Auger electrons, are the sources of information in a TEM. The output available from these sources includes images, diffraction patterns, and spectrometry data.




Figure 2.1 Schematic of TEM
[Ref. 2]

If a sample is crystalline the incident electrons will be Bragg diffracted by the periodicity of the structure producing spot and Kikuchi patterns. Convergent beam electron diffraction (CBED) patterns can also be produced. An analysis of the spot and CBED patterns gives information about the crystal structure of the sample as well as the lattice repeat distance. This, along with spectrometry data, often allows the full characterization of a TEM sample.[Ref. 1]

One type of spectrometry data, parallel electron energy loss spectroscopy (PEELS), identifies the composition and structure of the sample by analyzing the inelastically scattered electrons that are transmitted through the sample. These electrons have different energy losses, referenced to the incident beam energy, based on which atoms they interacted with in the sample. Analysis of the number of electrons with a given energy loss allows the composition of the sample to be identified. Besides elemental information certain characteristics of a PEELS spectrum, known as the energy loss near edge structure (ELNES) and extended energy loss fine structure (EXELFS), may be analyzed to give information about electronic bonding and thus phase information about the sample. The other type of spectrometry data, energy dispersive x-rays, cannot determine phase information directly. This is the data analyzed in this thesis and is described in more detail below. [Ref. 1]

B. ENERGY-DISPERSIVE X-RAY (EDS) ANALYSIS

In a TEM, x-rays are created through inelastic interactions between the incident electron beam and the sample. This creates two types of x-rays, characteristic and Bremsstrahlung. Characteristic x-rays are those that develop due to interactions with the inner electrons of the atoms and Bremsstrahlung are due to the interaction of the beam with the nuclei of the sample atoms. A summary of how characteristic x-rays are created

explains why EDS analysis is a useful tool for chemical analysis. As a first step it is necessary to review some of the basics of electron shell theory.

The arrangement of electrons around an atom can be described in a simple way using shell theory. In this theory there are allowed energy states or shells that an electron can occupy in an atom and each shell can only hold a certain number of electrons. Figure 2.2 is a two dimensional schematic of an atom with three electron shells shown. By historical convention the innermost, and lowest energy, shell is the K shell, the next is the L shell, etc. These shells are the only allowed energy states for the electrons; they cannot have an energy that corresponds to the energies between the shells. Since the allowed energy states are discrete, an electron must receive energy equal to the energy difference between the two shells if it is to transition to a higher energy shell. Likewise, if it is to drop to a lower energy shell it must lose energy equal to the energy difference between the two shells. An atom likes to be in the lowest energy state possible, called the ground state. This corresponds to having all electrons in the lowest energy shells possible. If an atom finds itself in a higher energy state it will try to return to the ground state. One way of doing this leads to the generation of characteristic x-rays.




Figure 2.2 Creation of characteristic x-ray

The atoms in a TEM sample will be in a ground state until the electrons from the microscope beam interact with the sample. If an electron in the beam penetrates the outer electron shells of a sample atom it can have an inelastic "collision" with an inner electron. If this interaction results in enough energy being passed to the electron then it will be ejected from its shell leaving a hole behind. The atom is now in a higher energy state and must find some way of returning to the lower energy ground state. This is done by the transition of an electron from a higher energy shell to the energy shell with the hole. The energy that the electron loses in making this transition must be used in some way. The generation of an x-ray with energy equal to the energy difference between the two shells is

one possibility. The other is the emission of an Auger electron(s) which will not be discussed here. Figure 2.2 shows an example of characteristic x-ray generation. An electron from the incident beam ejects an electron from the K shell. Another electron from the L shell transitions to the K shell, filling the hole. To conserve energy a K_{α} x-ray is generated. If the electron that filled the hole came from the M shell the x-ray generated would be a K_{β} x-ray. Figure 2.3 shows some of the possible transitions and the characteristic x-rays generated. [Ref. 1]




Figure 2.3 Some types of characteristic x-rays produced

As discussed previously all of these x-rays will have energies equal to the energy difference of the shells. It is also true that each element has a unique shell structure. This leads to a very useful fact; the x-rays created by electron/atom interactions have energies

that are characteristic of the atom in which they were created. In a multi-element sample each element will produce x-rays in proportion to the amount of that element in the sample.

How is this information collected? An EDS detector, located in the TEM above the sample, detects the x-rays given off, analyzes their energies and stores that information. The detector is a reverse-biased p-i-n diode, usually a silicon-lithium semiconductor. An x-ray emitted from the sample that hits the detector creates multiple electron-hole pairs in the semiconductor, the number of which is proportional to the energy of the x-ray thus identifying the x-ray's energy. The range of detectable x-ray energies is on the order of tens of kV. The total energy range of the detector is broken into bins or channels of a certain width in volts. The bin size depends on the total energy range of interest and the number of channels. For example, if the total energy range of interest is 29 kV and the number of channels is 2048 then the energy per channel would be 14.1 volts. If an x-ray is detected with an energy that falls within a particular channel a count is stored in that bin in the detector's multi-channel analyzer (MCA). The output, an EDS spectrum, is the number of counts or x-rays detected, per energy channel. Figure 2.4 shows an example of an EDS spectra. The y-axis is in counts and the x-axis is in energy, broken into discrete bins.[Ref. 1]

Both types of x-rays are detected, characteristic and Bremsstrahlung. Characteristic x-rays form peaks at specific energies. Since these x-rays have energies that are representative of their source atoms these peaks indicate what elements are present.

Bremmstrahlung x-rays create a background that is usually subtracted from the characteristic peaks when the spectrum is analyzed. If the spectrum is taken from a point where the sample is a single phase then the composition of that phase can be found. If this point in the sample has more than one phase this is no longer possible; the amount of each phase in the sample cannot be determined directly from a spectrum. In this case the amount of each element present is the only information available.[Ref. 1]




Figure 2.4 Example of an EDS spectrum

C. PRINCIPAL COMPONENT ANALYSIS (PCA)

Principal Component Analysis (PCA), one form of Multivariate Statistical Analysis (MSA), was initially developed by Karl Pearson in 1901 and further developed by Harold

Hotelling in 1933. It is a linear reduction technique; a large correlated data set is described using a new reduced set of uncorrelated axes or principal components. If a data set consists of n points, or spectra, each of which have p dimensions, or energy channels, PCA finds a set of p orthogonal axes that describe the data set. In addition these axes are weighted. The first axis contains most of the information in the data set and the amount of information in each subsequent axis decreases. If the data set were highly correlated it is possible for almost all of the information in a data set to be contained in q axes where $q \ll p$; the data set can now be described in a reduced dimensional space. This technique can be used on any large data set that is correlated in some way. In this thesis the data sets consist of a series of spectra taken across an interface.

Perhaps the easiest way to understand what PCA does is to look at a graphical example. Let there be a system that has two variables, A and B . If an observation of the system is made what you observe is the value of A and B at that point. Figure 2.5 shows the distribution of ten observations of the system in A and B component space. Now a principal component analysis is done on the data set. PCA will choose its first axis, or principal component, such that this axis describes most of the information in the data set. This corresponds to minimizing the distance of each data point to the first principal component. The second principal component is chosen such that it also describes the maximum amount of information. It has the additional criteria that it must be orthogonal to the first principal component. Each additional principal component is constructed using those two criteria; they must contain the maximum amount of information and be

orthogonal to all other principal components. The total number of principal components is equal to the number of variables in the system. In this case since there are two variables there are only two principal components. If the data set consists of thousands of variables, energy channels in an EDS spectrum, then there will be that many principal components. If the original data set was highly correlated, however, most of the information will be concentrated in the first few principal components. In this example the data sets follow a linear distribution and this information is now "concentrated" in the first principal component. These two facets of PCA, orthogonality of the axes and concentration of information in the first few axes, are what makes PCA a useful technique in studying TEM spectral data. [Ref. 3]




Figure 2.5 2D Graphical PC example

PCA is not the only linear reduction technique available. Another technique used extensively in studying spectroscopy data is factorial analysis of correspondence. The two differ in the metric used to describe the data. PCA uses a Euclidean metric while factorial analysis uses a χ^2 metric [Ref. 4]. A detailed mathematical description of both and a technique for making the two synonymous are given in [Ref. 4]. Although both techniques have been used all the work done for this thesis was done using PCA and the nomenclature used throughout is from this technique to avoid confusion.

D. PCA OF TEM SPECTRAL DATA

As stated previously, PCA is especially useful in the study of large correlated data sets. A series of spectra is precisely this sort of data. In a well-prepared sample the largest source of information is the compositional content of the specimen. If, instead of one spectrum, the data consists of a series of spectra then the largest source of information will be the variation in composition in the series. By its nature this will be a correlated data set. For example, in a series of EDS spectra the elemental peaks that correspond to a phase will rise and fall together, they are correlated, as the amount of that phase in a spectrum changes. The peaks of another phase may move in the opposite direction, they are anti-correlated, with the first phase; more of one phase usually means less of another. This leads to data sets that are well suited to a Principal Component Analysis or any other linear reduction technique. These correlations and anti-correlations, the change of the

amount of each phase in each spectrum, should be the dominant sources of information and be the major source of information in the first few principal components. Research in spectroscopy has exploited this concentration of the useful information of a data set for the past decade.

The research into the use of linear reduction techniques can be broken into two endeavors, elemental mapping [Ref. 4-10] and phase mapping [Ref. 13-16]. Elemental mapping research has been concentrated into three areas, useful signal and background/noise separation, identification of the information sources for each of the principal components and the study of the correlation/anti-correlation of elements. Phase mapping has used an extension of PCA, oblique analysis.

In any spectrum there are going to be at least three sources of information, the chemical composition of the sample, the background signal, and noise. These last two must be removed if an analysis of the underlying signal is to be done. A standard technique for doing this with electron energy loss spectroscopy (EELS) data obtained in the TEM is to assume that the background follows a model, one of the most popular being a power law model, AE^{-R} , where E is the energy loss and A and R are variables that must be estimated from the data [Ref. 5]. Linear reduction techniques are able to isolate the useful information from the background/noise without the use of a model and the spectra can be reconstructed using only the principal components that correspond to composition information creating background/noise free spectra [Ref. 5, 6]. This can be taken even

further by using the isolated composition information to construct "fictitious" images by extrapolation or interpolation [Ref. 7].

In some cases, besides separating the useful information in the first few principal components it is also possible to identify the source of information that is responsible for each significant principal component [Ref. 6, 8, 9]. Using this technique it has been shown that it is possible to reconstruct the elemental segregation at a grain accurately enough that it matches conventional techniques [Ref. 8, 9]. It needs to be pointed out, however, that the assumption of orthogonal information sources cannot be made for all data sets and it is possible that there can be more than one source of information contributing to any given principal component [Ref. 8].

The use of PCA on x-ray spectra leads to another possible way of analyzing data. There are no negative peaks in a normal x-ray spectrum but a principal component of x-ray spectra data does have negative and positive peaks that may show the correlation and anti-correlation of the elements [Ref. 8-10]. This can be used to show the preferential segregation at a grain boundary accurately in some cases [Ref. 10].

The research into phase mapping uses an extension of PCA called oblique analysis. An oblique analysis is the creation of a basis or coordinate system where the axes are not orthogonal. This is used since the physical sources of information may not be orthogonal, i.e. they can be 'oblique'. The possibility of using an oblique analysis to find the physical sources of information in a spectra series has been discussed in general terms for the past decade [Ref. 4, 11, 12]. If the physical sources of information are not orthogonal the

principal components of the data will be mixtures of the sources of information which precludes mapping phases using just one principal component. One way of extracting the physical components from the data in PC space is to have prior knowledge of the composition of at least one data point [Ref. 12]. This may not be particularly useful, the answer is known before the question is asked [Ref. 12]. In trying to map interface reaction phases an automatic oblique analysis, to use the nomenclature of [Ref. 12], is developed. The constraints used in this analysis are discussed in the next chapter. This technique has been applied to EELS [Ref. 13,14] and EDS [Ref. 13, 15,16] spectral data. This thesis was done in conjunction with the work on EDS data to help develop this phase reconstruction technique.

III. MODELED DATA SETS OF KNOWN COMPOSITION

A. PCA AND CHANGE OF BASIS

A principal component analysis develops an orthogonal basis that describes a data set in its entirety. It also isolates most of the correlated information in the first few principal components, called the significant principal components (PCs). The number of significant PCs depends on how correlated the data was, the more correlated the data the fewer the significant principal components. If the data set consists of a series of EDS spectra acquired from a TEM sample then the major contributors to the information in the significant PCs are the chemical composition changes in the sample. All of the uncorrelated information, noise and background, tend to be in the tail PCs as discussed earlier, unless they are a significant source of information [Ref. 5]. If only the significant principal components are considered, then PCA has taken the composition data, orthogonal or not, and created an orthogonal set of axes that also describes the chemical composition changes of the sample. This can be thought of as a change of basis; it has taken data points, the spectra, and found another coordinate system that can also be used to describe them. Unfortunately, the principal components have no physical meaning by themselves and can be difficult or impossible to interpret directly. This is especially true if a principal component is representative of more than one piece of information [Ref. 8]. What this thesis develops, in conjunction with [Ref. 13-16], is a technique to go from principal component space back to physical component space where the axes are the components, elements or phases, that are varying in the sample. As an example, consider

Figure 3.1. A unit vector along axis A represents the spectrum of element A, likewise, a unit vector along axis B is the spectrum of B. The ten data points are spectra with varying amounts of A and B. If the two principal components are found using PCA on the ten data points, then A and B can be found using a change of basis.

The mathematical process for a change of basis is shown here for a two variable/axis system, but it is a simple process to extend it to more variables/dimensions. Any data point in a coordinate system can be written as a sum of all axes multiplied by the appropriate coefficients. For instance in Figure 3.1 the point x can be written, $x = a1 * PC1 + b1 * PC2$. In a different coordinate system the coefficients are obviously changed, x written in terms of the $[A,B]$ coordinate system would be $x = a' * A + b' * B$. If $a1$ and $b1$ are known but not a' and b' , then a change of basis can be used to find a' and b' provided the coefficients of A and B in PC space are known. For this example they are, $A = A1' * PC1 + A2' * PC2$, and $B = B1' * PC1 + B2' * PC2$. All coefficients are shown in Figure 3.1. The equation,

$$\begin{bmatrix} a' \\ b' \end{bmatrix} = \begin{bmatrix} A1' & B1' \\ A2' & B2' \end{bmatrix} \begin{bmatrix} a1 \\ b1 \end{bmatrix} \quad (1)$$

is used to find the coefficients a' and b' . [Ref.17]

The information that may or may not be available is the description of axes/elements A and B in PC space. In this chapter, cases where this information is assumed known are considered, the next chapter deals with cases where it is not known

and the axes A and B must be found. When the representation of the physical components is known in PC space, the unknown information is the distribution of those components in the data. The physical components can be either elements or phases, both cases are considered.




Figure 3.1 Data points shown with PC and physical space axes.

Another question is what type of spectral data lends itself to an analysis by PCA. In general, useful information may be gained by a principal component analysis of any sort of EDS data that has a compositional change associated with it. The work in this thesis uses data from an interface between two phases, with and without the presence of an interface reaction phase. Most of the tests done used modeled EDS data with Gaussian peaks representing the elemental characteristic x-ray peaks. The use of modeled data allowed the tests to be done where the correct answers were known and allowed small variations to be put into each test. No noise or background was input into the data, its

effect was not considered until experimental data was tested. First, elemental components were modeled and the ability to find the correct distributions was demonstrated. Next, phase components, where the same elements are found in more than one phase, were used.

MATLAB was used for all the computer code developed in conjunction with this thesis. The MATLAB m-file `princomp.m`, contained in the MATLAB statistics toolbox, was used to perform the PCA of the data. A thorough description of the function is found in [Ref. 18]. This m-file returns the principal components of the data, the scores or amount of each PC in each data point and the amount of information contained in each PC. A MATLAB routine was written to do the change of basis from PC space back to physical component space for an input data set.

B. ORTHOGONAL DATA SETS

The first data set used to test the PC/physical space change of basis was a modeled diffuse interface between two elements A and B. Each EDS spectra was one hundred channels wide and both elements were Gaussian distributions of equal height, shown in Figure 3.2. These components are orthogonal, meaning that the spectrum peaks of the elements do not overlap. All cases considered here consist of these sorts of components; non-orthogonal data is considered in the next section. The data set consisted of ten spectra with A and B distributed as shown in Figure 3.3. After the PCA of the data set the information was partitioned in the principal components as shown in Figure 3.4. This is a scree plot and is a useful tool for determining which PCs are significant [Ref. 8]. The first

two principal components contain more than 99% of the information of the original data set, these two principal components are shown in Figure 3.5. The first principle component is the “average” of the data; it shows the presence of all the peaks with their orientation all in the same direction, positive in this case. For most data sets this is the first PC, in other words it usually contains the most information. In some data sets, where the data is heavily biased by one or more phases, this is not the case, as will be seen later. The second PC is easily interpreted as showing the anti-correlation of the elements. Included in the data set was a spectrum of both pure element A and B, see Figure 3.3, so the representation of the physical component axes, A and B, is known in PC space. These, along with the coefficients of each spectrum in PC space, are used for the change of basis to physical component space. The components were already known so the only unknown information was the distribution of the components. The results are compared to the input distribution in Figure 3.6, they match almost exactly. The lines are the input distributions and the symbols are the reconstructed distributions of A and B. The spectra of elements A and B have also been reconstructed almost exactly, Figure 3.7, where the symbols are the reconstructed spectra. This was a highly idealized test but does show, that in principle, PCA can be used to find the distribution in a diffuse interface by a change of basis to physical component space.




Figure 3.2 Spectra of input elements




Figure 3.3 Distribution of elements A and B




Figure 3.4 Amount of total information in each PC




Figure 3.5 Principal components of data set




Figure 3.6 Reconstructed distribution of A and B vs. input distribution




Figure 3.7 Reconstructed spectra vs input spectra

The next test is an extension of the first but with a third element present in the interface region. Once again the elements, A, B, and C, are modeled as Gaussian peaks of the same height and there is no overlap of the peaks, they are orthogonal sources of information. The spectrum of each of the elements is shown in Figure 3.8 and their distribution is shown in Figure 3.9. The scree plot, Figure 3.10, shows that there are three PCs with significant amounts of information, the total of the three is greater than 99%. These three principal components are shown in Figure 3.11. The care that must be used in interpreting the meaning of the PCs is illustrated in this example. PC3 shows element C anti-correlated with A and B, which is true in the data set. It would not be correct to assume that in some instances elements A and B are correlated because of their relationship in this principal component. Once again the elements A, B, and C, have a spectrum that consists of 100% of each element, see Figure 3.9, so the description of the physical space axes are known in PC space. The change of basis was performed and the resulting distribution of the three elements is compared with the input in Figure 3.12. The distribution is reconstructed by the PCA analysis and change of basis as were spectra of A, B, and C, shown in Figure 3.13.




Figure 3.8 Spectra of input elements




Figure 3.9 Distribution of elements A, B, and C




Figure 3.10 Amount of information in each PC




Figure 3.11 PCs of 3 element data set




Figure 3.12 Reconstructed distribution vs. input distribution




Figure 3.13 Reconstructed spectra vs. input spectra

In the first two tests each element contributed approximately the same amount of information to the data set. Elemental information is defined as the area under an element's spectrum peak multiplied by the amount of the element in all spectra, this is roughly equal for all elements in each of the data sets considered thus far. In the third test the result of decreasing the information of one of the elements was tested. This can be done in two ways, decreasing the amount of the component in the data set or decreasing its peak height. In this test the peak height of element C was made one tenth the other two elements. This lowered the amount of information supplied by C but leaves a spectrum that contains only that element. The distribution of the elements was kept the same as the second test, shown in Figure 3.9, so the total information supplied by the element C was one tenth that of elements A and B. The spectra of the elements are shown in Figure 3.14. The scree plot, Figure 3.15, shows the information content of each PC. Only the first ten principal components are shown, the rest also contain almost no information. Compared to Figure 3.10, the third PC is still significant but contains less information than in the test with equal peak heights. The information content of the first two PCs has increased so the total amount in the first three PCs is still greater than 99%. Figure 3.16 shows the principal components of the data set. It is interesting to note that the first PC, which contains the most information, is not the "average" PC, the principal component that shows all the peaks correlated. This was the case for the first two tests but here the "average PC" contains 42% of the total information while PC1 contains 47% of the information. Throughout this thesis although some general comments are made on the

nature of the PCs the source of the information in each significant principle component is not of great importance. It has been assumed that all the significant PCs are due to composition changes, this is the only information needed. As can be seen in Figures 3.17 and 3.18 the input data is reconstructed almost exactly in spite of the reduced information contained in the interface element.




Figure 3.14 Spectra of input elements




Figure 3.15 Amount of information in each PC




Figure 3.16 Principal components of data set




Figure 3.17 Reconstructed distribution vs. input distribution




Figure 3.18 Reconstructed spectra vs. input spectra

It has been shown that the principal components of a data set consisting of a series of EDS spectra can be used to obtain elemental information about the sample. This seems to be independent of the information contained by each element in a data set, as long as the elemental spectra are orthogonal. Although this data is relatively easy to obtain by other means using EDS spectra this is not the case where the components are no longer elements but are phases. In this case, as discussed previously, EDS data only gives the elemental composition of a sample. The next section uses the same type of distribution as the elemental component tests, a diffuse interface, but the components are multi-element phases.

C. NON-ORTHOGONAL DATA SETS

In Figure 3.1 the physical components were the elements A and B. The peaks of their modeled EDS spectra do not overlap; they can be considered to be orthogonal sources of information. If the physical components are not elemental but are phases made up of differing amounts of A and B then the physical component axes system is no longer orthogonal. Figure 3.19 is a two dimensional example. The two phases, α and β , are both made up of elements A and B, so the basis described by them is not orthogonal. The data set taken as a whole, however, has not changed from the example shown in Figure 3.1 therefore the principal components do not change. What does change is the description of each point in physical space; the axes [A,B] and [α , β] are not synonymous. In this example, as in the rest of the tests in this section, there is a data point that corresponds to

each of the axes in physical component space, the unknown information is the distribution of the phases. These are the same criteria applied to the previous section of tests, what is being studied is the effect of non-orthogonal data on the reconstruction process.




Figure 3.19 Data points shown with PC and phase physical space axes.

The first test conducted consisted of three phases, α , β , and γ , each of which had the elemental composition shown in Figure 3.20. The interface phase, γ , consists of elements that are also in the other two phases. The information supplied by each phase is also roughly equal in this case, although it is slightly skewed to the two element phases. The distribution of the phases is shown in Figure 3.21. Figure 3.22 shows the information weighting of the PCs. On a linear scale there appear to be only two significant PCs that describe 97.6% of the information. Using a log scale it can be seen that the third PC is separate from the tail principal components, containing almost all of the remaining information. The three significant principal components are shown in Figure 3.23. Here

the interpretation of the PCs has become even more difficult. The second PC seems to show the anti-correlation of phase α and β , but there is no direct interpretation of PC3 that can be made concerning the correlation of the component phases. After executing the change of basis using data points or spectra, one, six, and eleven as the axes, the reconstructed distributions matched the input almost exactly, Figure 3.24. The reconstruction of the spectra that correspond to the physical component axes is shown in Figure 3.25, also a very good reproduction of the input. In this case where each phase supplies approximately the same amount of information, the non-orthogonality of the physical components is not a factor. An accurate reconstruction of the input data is accomplished including the correct distribution of the phases.




Figure 3.20 Spectra of input phases




Figure 3.21 Distribution of phases




Figure 3.22 Amount of information in each PC




Figure 3.23 Principal components of data set




Figure 3.24 Reconstructed distribution vs. input distribution




Figure 3.25 Reconstructed spectra vs. input spectra

Next, the amount of information contributed by the interface phase was decreased. This was done in the same way as in the previous section, the interface phase's peak heights were reduced in relation to the peak heights of the bulk phases; the peak heights of α and β were increased by a factor of five. The spectra are shown in Figure 3.26. The distribution was kept the same as the previous test, shown in Figure 3.21. Once again a log scale is necessary to see that the third PC is significant, Figure 3.27, in this case it contains 0.4% of the total information, and the first two PCs account for greater than 99%. The three principal components are shown in Figure 3.28. Any attempt to interpret these PCs would most likely result in the assumption that the components are elemental and not phases; there is not any easily seen evidence of phases in the PCs. The data is

biased to the extent that any interpretation of the PCs is unlikely to result in any useful information without prior knowledge of the data. Although the data is skewed towards the bulk phases the change of basis back to physical space does give the correct distribution of the phases, Figure 3.29. The reconstruction of the spectra using the principal components is starting to show the effects of the skewing of the data, especially for phase γ . Figure 3.30 shows the reconstruction of the component spectra. The data has become dominated by the other phases and, unlike the elemental cases, this affects the reconstruction. The cause of this is directly related to the non-orthogonality of the components, α and β which is masking the presence of γ .




Figure 3.26 Input phase spectra




Figure 3.27 Amount of information in each PC




Figure 3.28 Principal components of data set




Figure 3.29 Reconstructed distribution vs. input distribution




Figure 3.30 Reconstructed spectra vs. input spectra

In the next test the amount of information of the interface phase is reduced again; the bulk phases have a maximum intensity of ten creating the spectra shown in Figure 3.31. The distribution of the phases is the same as the previous non-orthogonal cases. The further reduction of information of the interface phase has increased the information the first two PCs. They now contain 99.9% of the data while the third has only 0.1%. Figure 3.32 shows the scree plot of the PCs, Figure 3.33 shows the principal components themselves. As with the previous test the phase distribution has been reconstructed, Figure 3.34, but the reconstruction of the phase spectra has degraded even further, Figure 3.35. Phase γ has contributed such a small amount to the information of the data set that it is not significant. This degradation of the reconstructed data does seem to be strongly related to the reduction of the total data of the interface phase. The three tests of non-orthogonal data given here show a progression of the degradation of the reconstruction, rather than a cut-off where the interface phase becomes insignificant. The distribution can always be reconstructed because of how the tests were conducted. Spectra numbers one, six, and eleven were defined as the axes in physical space. These spectra are no longer reconstructed accurately using the principal components but all the spectra reconstructed from the PCs have the same distribution of these spectra as the actual data does of the component phases. The next section studies data normalization techniques to see if the information content supplied by γ can be increased by data manipulation.




Figure 3.31 Spectra of input phases




Figure 3.32 Amount of information in each PC




Figure 3.33 Principal components of data set




Figure 3.34 Reconstructed distribution vs. input distribution




Figure 3.35 Reconstructed spectra vs. input spectra

D. NORMALIZATION TECHNIQUES

As shown in the previous sections, if one of the phases contributes a small enough amount of information to the total, that phase becomes statistically insignificant. The reconstruction of the data set by a change of basis of the significant principal components no longer gives reliable results. This section studies the effects of normalizing the data before a principal component analysis is done. This was done to determine if there was a normalization technique that removes the bias of the data towards one or more of the phases and allows the change of basis to reconstruct the data correctly. Five different normalization techniques were studied.

The data itself is an $n \times p$ matrix, where n is the number of spectra and p is the

number of channels. Normalization can be done to each column, p , or to each row, n . Both types are considered. Three types of column normalization were attempted, two that considered each channel independently and one that normalized the channels according to the elemental peaks. The first case normalizes the total intensity in each channel. The sum of the intensity over all spectra is computed for each channel and the intensity of each channel is divided by that number. For the second case each channel was divided by the channels standard deviation over all spectra. The elemental peak technique summed the total intensity of all channels in each elemental peak over all spectra and divided each channel in the peak by that number. The PCA was then done on the data set, the data was reconstructed, and then the normalization was removed. The results were then compared to the previous test of the unnormalized data. The last technique was normalizing the total intensity of each spectra to one, dividing each channel in each spectrum by the total intensity in that spectrum. Again the PCA was carried out then the normalization was removed and the reconstructed data was compared to the original case. The last data set, shown in Figures 3.31-3.35, was used in these tests.

The results showed that the column normalization techniques did not change the output of the change of basis to any noticeable extent. The reconstruction of the component phases does not change from that of the unnormalized case, shown in Figure 3.35. Table 1 shows the amount of information in the first three principal components for each of the normalization techniques as well as for the unnormalised data. Only data point, or spectra, normalization has raised the amount of data in the third PC by any amount, a

factor of ten. Figure 3.36 shows the reconstruction of the component phase spectra using this normalization technique, there is a significant improvement. An explanation for this is based upon the fact that there is a spectrum that includes only phase γ . In the original data set this spectra had a total intensity that was much less than the spectra with significant amounts of α and β . After data point normalization this spectrum is now on par with the others in terms of total intensity, as are the others that contain a large amount of γ . This change in relative intensity makes γ statistically significant, its contribution is now captured in the principal component analysis.

	None	Col. Sum	Col. std. dev.	Peak Area	Data Point
PC1	0.661	0.696	0.666	0.683	0.651
PC2	0.338	0.303	0.333	0.317	0.334
PC3	0.001	0.001	0.001	0.001	0.015

Table 1. Amount of information in significant PCs for each of the normalization techniques




Figure 3.36 Reconstructed spectra vs. input spectra

The use of non-orthogonal data has reduced the ability of the combination of PCA and a change of basis to accurately determine the physical components. This increases as the data becomes biased towards one or more of the components. One normalization technique, data point, does seem to reduce this bias enough so that the reconstruction of the data set is accurate. The tests done in this chapter do have the limitation that the composition of the elements and phases being looked for are assumed known. In most real world cases this is not true. The next chapter removes this limitation, it allows for one of the phases to be unknown and searches for the unknowns in PC space.

IV. MODELED DATA SETS OF UNKNOWN COMPOSITION

A. SEARCH ROUTINE AND PHYSICAL SPACE CRITERIA

The previous chapter studied data from a modeled interface between two bulk phases. It was assumed that the composition of these phases and the composition of the interface phase, if present, was known. In this chapter the last assumption, knowledge of the composition of the interface phase, is removed. In a diffuse interface it will not usually be possible to isolate the interface phase in an EDS spectrum so its composition cannot be determined using EDS data in the conventional way. This chapter extends the PCA/change of basis technique to cases where one of the physical components is unknown, such as at an interface, and tries to find that phase's composition and distribution.

Consider the two element data set consisting of the EDS spectra shown in Figure 3.19. What would be obvious by looking at the data set is the variation of elements A and B from spectrum to spectrum; this variation is one way to describe the data. Let us assume, however, that the data is taken from an interface of two phases, α and β , shown in Figure 3.19, and that the composition of these phases is not known. The information that is needed, then, is the composition and distribution of these phases in the data set. This is not directly available from EDS spectra. If the description of the two phases in PC space was known then each of the spectra in the data set could be described in terms of the two phases by a change of basis as described in the last chapter. Since their composition is unknown, the description of α and β in PC space is not known and this information must be searched for. If $a1 * PC1 + b1 * PC2$ is calculated for all possible

values of $a1$ and $b1$, all possible combinations of PC1 and PC2 have been calculated, and embedded in these combinations will be the spectra of both α and β . The question then becomes how are the correct answers separated from all the other incorrect ones. Because the answers must be physical in nature there are some constraints that can be applied to the reconstructed spectra. First, an EDS spectrum is a measure of x-ray counts per energy channel; there are no negative values in a spectrum. Any combination of the PCs that has a negative intensity can be discarded. Other limiting criteria are found when the data set spectra are described by the reconstructed phases. Each spectrum, x , is described in $[\alpha, \beta]$ space by $x = a' * \alpha + b' * \beta$, where a' and b' are the amount of α and β needed to reconstruct the spectrum x . If a spectrum is all β , for instance, then the coefficients would be, $a' = 0.0$ and $b' = 1.0$. The most a phase can contribute to a spectrum is 1.0, that spectrum is that phase, and the least it can contribute is 0.0, that phase is not present in that spectrum. If a spectrum is made up of a combination of α and β then the coefficients must add up to 1.0. The coefficients are percentages of the total information in the spectrum, said to be 100%, as such the combination of the two coefficients must describe all the information of the spectrum, there cannot be a combination of the phases that equals 70% or 130%. With these criteria in mind, all the combinations of the PCs are used to reconstruct each spectrum of the data set. Each reconstructed spectrum is tested using the above criteria and any that fall outside of those limits are discarded. Since α and β are real spectra and are the phases whose variation describes the data set they should pass all of the above criteria.

In practice there must be some tolerances in the criteria when a phase is being searched for. The search routine uses discrete points, or coefficients in PC space, to reconstruct a possible phase spectrum and it is highly unlikely that the point that corresponds to the exact answer will be chosen. More likely points near the correct point in PC space will be tested. These correspond to spectra that are close to, but not perfect replicas of, the correct answer. These spectra will reconstruct the data set but with some inexactness so tolerances in the criteria are used to allow the general area of the correct answer to be found. With actual data another problem that necessitates the use of tolerances in the selection criteria is that chemical composition changes are not the only source of information. Thickness variations, for example, are a source of information in a TEM sample that could be present in the significant PCs. Although not giving rise to large amounts of information, these other sources must be compensated for.

There are three tolerances that are used in the tests of the combinations of the PCs that are reported using the format [X:Y:Z]. What these variables refer to can be illustrated using the equation $x = A1 * \alpha1 + B1 * \beta1$, where x is a data set spectrum, $\alpha1$ and $\beta1$ are two combinations of the PCs that are being tested, and $A1$ and $B1$ are the coefficients that are necessary to reconstruct x correctly using $\alpha1$ and $\beta1$. X is the amount that the coefficients, $A1$ and $B1$ in this example, are individually allowed to be less than 0.0 or greater than 1.0. Y is the amount that the sum of the coefficients, $A1+B1$, is allowed to differ from 1.0. Z is the maximum negative intensity of the reconstructed spectrum x . All combinations of the PCs that pass the criteria within the tolerances [X:Y:Z] are saved as a

possible phase spectrum. This allows an area of PC space to be identified that contains possible answers without finding the exact point. In conducting the tests the tolerances were set fairly loose on the first run to identify a portion of PC space to search more closely, then this area was searched one or more times with tighter tolerances to find possible spectra that met whatever tolerances were deemed adequate. This allowed a finer search in the area of the highest probability of finding correct answers without wasting computation time on areas that did not contain any combinations of the PCs that resembled an EDS spectrum.

B. ORTHOGONAL TEST

The first data set tested was the elemental/orthogonal data set shown in Figures 3.9 and 3.14-3.16. In this case the interface element has one tenth the intensity of the other two elements. The two bulk elements were assumed known and the axes, or spectra, that correspond to those elements were specified. The interface axis was searched for using the criteria described previously. In this case, as in the rest of the tests, the block of PC space to search was found in the following manner. After the principal component analysis each spectrum in the data set was described by the PCs, $x = a1 * PC1 + b1 * PC2 + c1 * PC3$, for example, where x was a spectrum in the data set. Each spectrum has it's own set of coefficients. The maximum positive and negative coefficients of the PCs in the data set were multiplied by two and these numbers were chosen as the bounds for the initial search of PC space. Once a likely area of PC space had been identified the search was narrowed

to that area, as discussed above. In this case there were two known components and one unknown, so three principal components are used; a three dimensional cube of PC space is searched. This was true of all the tests considered in this chapter, there were always two known phases, the bulk phases, and one unknown, the interface phase. The block was then broken into a number of points, the more points the finer the search. In this case, the search resulted in a group of answers for the interface element in PC space shown in Figure 4.1, using the tolerances [0.05:0.05:-0.05]. The cluster of answers extend from -0.10 to 0.10 on the first principal component, from -0.02 to 0.15 on the second, and -0.26 to -0.23 on the third. The PC space coefficients of the spectrum that consists of 100% of the interface phase are (0.00, 0.00, -0.24). The PC reconstruction of the data set was close to the input data, the bias of the data did not affect the reconstruction, so these coefficients are a good approximation of the actual point in PC space that describes the interface phase exactly. The coefficients of the spectrum, shown in Figure 3.17 and 3.18, lie within the limits of the possible answers in PC space. The other points found in PC space have the same element C peak height as the correct answer, but each has larger negative peak for elements A and B. These peaks vary for each answer but are always within the tolerance set. The physically meaningful part of each spectrum, the element C peak, is the same for all answers in the set. If the negative peaks are discarded then they all describe the same answer, in effect the whole area of PC space reconstructs the correct answer. The tolerances for this case were chosen so they were large enough to allow more than one answer to be found but small enough that all answers found had the same

positive peak. In this case, where the data is orthogonal, the selection criteria used to pick physically meaningful reconstructed interface spectra are sufficient to localize the correct answer so that all possible answers found have the correct size peak for element C.




Figure 4.1 PC space coordinates of possible spectra

C. NON-ORTHOGONAL TESTS

Non-orthogonal data was tested starting with the data set shown in Figures 3.20-3.23, where α and β were the known phases and γ the unknown. The results of the search of PC space are shown in Figure 4.2, using the tolerances $[0.1:0.1:-0.1]$. The viable answers for γ are no longer clustered around a single point but are spread out along a line in PC space. The size of this cluster depends on the tolerances used in specifying the criteria, the looser the tolerances the more points, but its shape remains roughly constant. It is a mistake, however, to make the tolerances as tight as possible until only one answer remains; the correct answer is not always the one with the tightest tolerance. Even if the

exact point in PC space is tested it is being combined with the PC space representation of the bulk phases which are not exact replicas of the actual bulk phase spectra. This makes the change of basis with the correct answer slightly inaccurate and allows answers that are close to the correct answer that meet the selection criteria to have tolerances on par with it. What this cluster in PC space corresponds to is multiple answers for the interface spectrum all of which satisfy the selection criteria. Each answer found is a small variation on its immediate neighbors with the difference in the spectra growing as you get farther away. The data set was constructed with a spectrum of the interface phase whose PC space coefficients are (3.03, -1.04, -0.91). The group of possible interface spectra extend from 2.69 to 7.21 on the first principal component, -1.38 to 2.79 on the second, and -4.83 to -0.73 on the third. The correct interface phase is shown in Figures 3.31 and 3.21. Two other answers from the cluster of possibilities in PC space are shown in Figure 4.3, with their distributions shown in Figure 4.4. Obviously the other possibilities vary enough from the correct answer as to be a different phase entirely. There is nothing in the criteria specified thus far that allows one answer to be chosen over the others, barring prior knowledge of the correct answer. Normalization techniques developed in the previous chapter were used to evaluate the data to ascertain if any of these would isolate the correct answer. Each normalization technique was used on the data set and the answers found using the same tolerances as the unnormalized case were compared. All the different normalization techniques returned the same types of answers as the unnormalized case; the correct answer was embedded in a cluster of possibilities that had the same types of

variations. The data point normalization technique did seem to have an effect on the tolerances needed. To localize the correct area in PC space for all the other types, including unnormalized data, the search was run three times starting with the tolerances, $[0.4:0.4:-0.4]$. This was followed by searching the reduced area found in the first run by a run with the tolerances, $[0.2:0.2:-0.2]$, and finally $[0.1:0.1:-0.1]$. This was done because if the smallest tolerances were used first then the area of physical answers was missed; all the points within the area of physical answers that met the proper tolerances were missed. With data point normalization it was only necessary to do a run with the final tolerances, $[0.1:0.1:-0.1]$ to find a cluster of answers. By normalizing the data the data set has changed so the principal components of the data change. In this new PC space enough points are found by using the final tolerances initially that it was not necessary to narrow the search area first. Once the same tolerances were achieved, however, the answers found were the same in both cases. The non-orthogonality of the data has introduced a range of answers that cannot be differentiated from the correct answer with the selection criteria adopted.




Figure 4.2 PC space coordinates of possible spectra




Figure 4.3 Two other possible answers for interface phase




Figure 4.4 Distribution of other possible phases

The non-orthogonal case shown in Figures 3.31-3.33 was tested next. As before the two bulk phases, α and β , are assumed known and the interface phase, γ , is searched for. The extended region of answers for the interface phase found in PC space using the tolerances [0.1:0.1:-0.1] is shown in Figure 4.5. The extent of this cluster along the three PCs is -3.98 to -1.33 along the first PC, -0.10 to 3.57 along the second and -1.94 to -1.53 along the third. To ensure that the correct answer was contained within this group a search was performed based on prior knowledge of the answer. The result, with the PC coordinates (-1.73, 2.55, -1.53), is shown in Figures 4.6 and 4.7. This, in fact, is a better reconstruction of the input phase than was found in the previous chapter since the

reconstruction of the spectrum with 100% of the interface phase is not assumed to be the interface phase. Once again there is no way of differentiating between any of the answers using the criteria developed thus far. Although the correct answer is found as well, all the points are legitimate according to the test criteria.




Figure 4.5 PC space coordinates of possible spectra




Figure 4.6 Reconstructed spectrum vs. input spectrum




Figure 4.7 Reconstructed distribution vs. input distribution

Next, the same phase spectra were used with distributions that did not include a spectrum of 100% of the interface phase. The interface phase now has a maximum coefficient of 0.8, or 80%, in any spectrum. The distribution of the phases is shown in Figure 4.8. The principal components are very similar to those for the case where the data set had a spectrum of 100% of the interface phase. The peak heights of the PCs show a small change, Figure 4.9 compared to Figure 3.33, and the amount of information per PC has changed as well. In the 100% case the distribution of information in the significant PCs was 66.11%, 33.79%, and 0.10%, and in this case it has become 66.01%, 33.92%, and 0.07%. The reduction of information in the third phase has caused a reduction of information in the third principal component. Using the tolerances, $[0.1:0.1:-0.1]$, the possible answers for the interface phase found after the change of basis from PC space show a same spread very similar to the previous case with the range -5.86 to -1.00 on the

first PC, -1.14 to 4.43 on the second, and -1.86 to -1.29 on the third, Figure 4.10, and the correct answer is embedded in that space. This was verified by a search of all the possible answers using prior knowledge of the interface phase's composition.




Figure 4.8 Input phase distribution




Figure 4.9 Principal components of data set




Figure 4.10 PC space coordinates of possible spectra

In the last test the amount of information in the interface phase was reduced further, the same phases as the previous two tests were used with the distribution shown in Figure 4.11, giving the interface phase a maximum of 20% in any spectra. The distribution of information in the principal components is shown in Figure 4.12, only the first two contain a significant amount of information. The significant PCs, along with the third principal component, are shown in Figure 4.13. To do a change of basis to three physical components you must use three principal components even though there is not a significant amount of information contained in the third principal component. When a three phase change of basis was attempted a group of possibilities for third phase were found but all these answers had less than one tenth of one percent of that phase in any spectrum, they essentially did not exist in the data set. These answers did not include the

correct answer. The reason for this can be seen by studying the principal components. To reconstruct the correct interface phase a linear combination of the principal components must exist that gives equal heights of the left and middle peaks and none of the right peak. Using the principal components of this data set this is impossible, there is no PC that allows the subtraction of the right peak without the subtraction of the middle peak as well. In data sets that are not as biased as this one there is always a PC that has these two peaks anti-correlated so the correct interface phase can be reconstructed. In this case the amount of information in the data set contributed by the presence of the interface phase was so small that it was not statistically significant and is not present in the principal components.




Figure 4.11 Distribution of phases




Figure 4.12 Information content of principal components




Figure 4.13 Principal components of data set

This last data set raises the question of how to find the number of phases present in the interface if this is unknown. In all the previous cases the number of significant PCs corresponded to the number of phases. In this case, however, the input data contained three phases but because of the bias of the data there are only two significant PCs and the attempt to reconstruct the data with three phases failed. With experimental data the problem of identifying the number of phases by the number of significant PCs is complicated by the background, other sources of information, and noise. The number of significant PCs can probably be used as a guide to the number of interface phases but should not be taken as the absolute answer. A study of the PCs may help in determining the number of phases as well. In the previous test it is obvious that the third PC does not contribute any useful information just by examining that principal component. With experimental data the contribution of a PC is not as obvious but if the number of phases present is not known it should help in determining how to proceed.

If an interface phase contributes enough information to a data set the composition of that phase, and its distribution, can be found. Unfortunately, the criteria developed thus far are insufficient to positively identify the phase; more than one answer is found for the interface phase in PC space that fits the criteria. Furthermore, there is no way within the criteria to identify which phase is the correct one using the selection criteria. Other criteria or tests would need to be developed if the correct phase is to be identified. With the modeled data used here there is no other information available to do this. The data sets were created using the criteria described above to make them a model of EDS data but no

other restrictions were placed on their construction. Consequently, there is no other information that can be brought to bear to determine which of the possibilities in PC space is the correct interface phase. Using experimental data, however, there are other criteria that may be used to limit the possibilities further. These will be discussed in the next chapter where the PCA/change of basis technique is applied to experimental data.

V. EXPERIMENTAL DATA

A. DATA SET BACKGROUND AND PREPARATION

In this chapter the PCA/change of basis technique developed in the last two chapters is applied to experimental data; the data is no longer idealized Gaussian peaks of known composition. It has been shown that an unknown interface phase spectrum could be reconstructed but that it was embedded in other equally possible answers. Here, experimental data from an interface where some knowledge of a possible interface phase exists is used to try to verify the PCA/change of basis results of the previous chapter. How to further limit the results found now that experimental data is being considered is also discussed. The work done here was done in conjunction with Refs. 13-16 and the data is taken from the same TEM sample used in those studies.

A brief description of the preparation of the material that the sample data was taken from is useful in understanding the interface that is studied. A technique for metallizing chemically vapor deposited diamond (CVDD) using intermediate layers of Cr and Al_2O_3 allowing the use of CVDD as a substrate material for electronic packaging has been developed by Menon and Dutta [Ref.19,20]. To manufacture the sample the diamond was heated to 573-673K and held there while a 20-50 nm layer of Cr was deposited onto the CVD diamond followed by a 100-200 nm layer of alumina. An anneal at 673 K for twenty four hours was then performed. The Cr was expected to enhance the adhesion of the Al_2O_3 by reacting with the carbon to form a carbide and the oxygen to form an oxide during the deposition and the anneal. The Al_2O_3 and the Cr_2O_3 form a solid solution at

high temperatures and separate into a two phase mixture at low temperatures, bonding these two layers. If the Cr forms a carbide with carbon from the CVDD layer these layers will also be bonded. The final product would then be a CVDD substrate with a layer of chromium carbide followed by a layer of chromium oxide and finally a layer of alumina. Metallization is achieved by applying a fritted paste to the alumina layer. The interface of interest here is the C/Cr interface. Auger electron spectroscopy and a depth profile analysis on a C/Cr interface manufactured under the same conditions described here determined that a carbide layer, Cr_{23}C_6 , was created next to the CVDD. This Cr/C interface has the advantage that a possible interface phase has been determined and can be compared to the results of a PCA/change of basis analysis. An example of the interface of interest is shown in Figure 5.1. The interface phase is formed in the dark layer adjacent to the CVDD. [Ref. 19, 20]




Figure 5.1 Example of C/Cr interface

Two series of spectra were taken from different locations in this sample using a TOPCON 002B TEM with scanning transmission (STEM) capability and a LaB₆ emitter. The TEM is equipped with an EDAX Li drifted Si energy dispersive x-ray detector (EDS) (ultra thin window), an Emispec Vision system and a GATAN PEELS imaging filter. The first data set consists of nine spectra taken across the interface manually before the Emispec Vision system was installed with a 8 nm probe at 10 nm spacings for a total line scan of 80 nm. The Emispec Vision system and STEM capability were used to generate the second linescan of thirty-five EDS spectra using a probe size of 3 nm with 3 nm spacing for a line scan length of 112 nm. Both series of EDS spectra were taken along a line perpendicular to the Cr/C interface that started in the CVDD and ended in the Cr₂O₃. This gave sets of data similar to that studied in the previous chapter, two known bulk phases and an unknown interface phase. The EDS spectra data sets were downloaded in ASCII format and transferred to a desktop workstation and input into the MATLAB routine for analysis. A major assumption implicit in the PCA/change of basis technique is that chemical composition changes are the largest source of information contributing to the significant principal components. In an attempt to limit the amount of information contributed by other sources some steps to reduce the sources of information in the significant PCs were taken. Each EDS spectrum consisted of 2048 channels with a channel width of 10.0 V for the first data set and 14.1 V for the second data set for energy ranges of 20 kV and 29 kV respectively. Figure 5.2 shows the first 500 energy channels of a spectrum from the second data set, 0.0 to 7.1 kV with the elemental peaks of interest, C,

O, and Cr highlighted. First the background was deleted from the C-K, O-K, and Cr-K peaks. The average intensity value of a group of channels near each peak of interest was calculated and subtracted from the peaks. Every channel in a spectrum is a potential source of information but only the channels that correspond to the elements of interest will contribute composition information; they were the only elements present in the interface. To isolate this information, the peaks of interest, C-K, O-K, and Cr-K, were cut out of each sample spectrum and spliced together to form reduced energy channel data sets. There is an overlap of the O-K and Cr-L peaks so the intensity due to the Cr-L peak is included by default. The point of this thesis is to try to develop a technique where phases made up of the same elements can be differentiated in a set of EDS spectra. This is analogous to the situation with the O-K and Cr-L peaks and so the presence of the Cr-L peak should not affect the results. To try to ensure that noise was not a large contributing factor in the significant PCs one hundred second count times were used per spectrum in both data sets. As was seen in the previous chapters the amount of information that is contained in the third principal component, for a three component case, can be very small, and it is necessary to use long count times to try to ensure that this PC remains distinct from the tail PCs, those that contain a majority of the noise. Figure 5.3 shows the reduced channel spectrum of Figure 5.2 with only the C-K, O-K, and Cr-K peaks, in that order.




Figure 5.2 C/Cr₂O₃ interface spectrum




Figure 5.3 Reduced channel spectrum from Figure 5.2

B. EXPERIMENTAL DATA TESTS

The first data set consisted of nine spectra taken across the Cr₂O₃/CVDD interface manually with an 8 nm probe taken at 10 nm spacings for a total line scan length of 80 nm. The reduced spectra were created by extracting 18 channels in the range 171 V to 350 V

for the C-K peak, 25 channels from 391 V to 640 V for the O-K peak, and 35 channels from 5241 V to 5591 V for the Cr-K peak for a total of 78 channels. Figure 5.4 shows the first and ninth reduced spectra which were used as the bulk phase's spectra. The Cr_2O_3 spectrum does have a small amount of carbon. The Cr_2O_3 layer sits between the CVDD and the Al_2O_3 so a pure Cr_2O_3 spectrum cannot be obtained, there is always some amount of C or some contribution to the O peak due to the alumina. This spectrum represents a compromise, the contributions from both are small and the amount of Cr_2O_3 is maximized. The amount of information in each principal component is shown in Figure 5.5. There are three significant PCs and although the third is only barely above the noise level it is distinct from the noise. The breakdown of information is as follows, 78.54% in the first PC, 21.36% in the second, 0.05% in the third, and 0.04% distributed among the rest. This differs from the modeled data, there is some information in the tail PCs, although not a large amount, which is expected with the presence of noise in the data. The significant PCs are shown in Figure 5.6. The third PC is much noisier than seen previously but it does have a distinct middle peak which is indicative of composition information. The fourth principal component is shown in Figure 5.7 for comparison. The noise dominates this principal component and there are no recognizable peak correlations. A comparison of the first four principal components reaffirms what is shown in Figure 5.5, the first three PCs can be used for a reconstruction to produce three phases. The distribution of possible spectra in PC space that were found using the tolerances [0.2:0.2:-0.2] is shown in Figure 5.8. It is apparent that there are two planes of answers present in the possible solutions.

The upper plane is a set of answers that contain all three peaks but they have a negative amount, within tolerances, in each of the data set spectra. They correspond to constructing the data set with the two bulk phases and then subtracting a small amount of all three peaks to get the correct intensities. The same type of plane also existed in the modeled data, if the tolerances were made loose enough. With those data sets, the tolerances could be made tight enough so that they no longer appeared as possible spectra. As there is no positive contribution of these phases to any of the spectra, they are obviously non-physical and are ignored. It is possible to tighten the tolerances a small amount, to $[0.15:0.15:-0.15]$, but an attempt to tighten the tolerances to $[0.1:0.1:-0.1]$ produced no results. The last chapter showed that tightening the tolerances as much as possible could exclude the correct answer so this was not attempted here. The extent of the plane with plausible answers is 5.41 to 21.19 on the first PC, -3.20 to 1.82 on the second and -2.49 to -0.33 on the third. The spectra show a continuous variation in the ratio of the C peak to that of the Cr peak. There are some spectra with little or no C and as you move through the cluster the C peak grows in size until there is almost a 1:1 ratio in the peak heights. Figure 5.9 shows three answers taken from the possibilities. The top and bottom spectra show the extremes in peak height ratios and the middle spectrum shows a possible spectrum between these two. The other variation seen in the cluster is in the total intensity contained in each spectrum. The same peak ratios are repeated multiple times but with different peak heights for both peaks. As was stated previously each point is a small variation of its immediate neighbors with the difference growing the farther away in PC

space you are. There is no sharp dividing line between the possibilities so the three presented here are to show the trends of the data not to give definite answers. The distribution of all the points shown in Figure 5.8 is shown in Figure 5.10. There are groups of answers that have approximately the same amount of interface present. In each of these groups is a variation of the spectra shown in Figure 5.8, the groups do not break down according to spectrum type but according to the height of the peaks in the spectrum. Take, for example, the reconstructed interface phase that corresponds to Cr, this spectrum appears multiple times in PC space with a different peak height for Cr. The change in peak height creates a different maximum amount in its distribution, so that each group in Figure 5.8 has some spectra that correspond to this possibility with different peak heights. This is true of the other two spectra in Figure 5.6 as well, there are multiple possible distributions based on the intensity of the reconstructed peaks. Figure 5.11 shows the distribution of the bulk phases for all the cases shown in Figure 5.10. This shows that the distributions found for these two phases are also viable.

The answers seen here are of the same type that were found in the last chapter, meaning that there are multiple possibilities that cannot be differentiated using the selection criteria specified thus far. These answers vary from each other in two ways, the ratio of the peaks in the answers and the magnitude of those peaks. Fortunately, since the data is taken from an experimental sample there are other criteria available to differentiate the possibilities. The elements involved, C and Cr in this case for the most part, will only form certain compounds and these compounds will have definite peak ratios. This allows

at least some of the possibilities developed initially to be discarded. Even if all answers except for one were discarded this would still leave multiple copies of this answer each with a different total intensity giving a spread of possible concentrations in the data set. This can be overcome if there is some way to identify what the proper intensity for the phase should be based on the intensities of the bulk phases. These ideas are not pursued here but they should be capable of narrowing the rather broad possibilities found with the change of basis.




Figure 5.4 Input bulk phase spectra




Figure 5.5 Information content of PCs




Figure 5.6 Significant PCs




Figure 5.7 Fourth principal component




Figure 5.8 PC space coordinates of possible spectra




Figure 5.9 Three possible interface phase spectra




Figure 5.10 Possible interface phase distributions




Figure 5.11 Possible bulk phase distributions

The next data set was taken as a line scan at a different point along the interface with a 3 nm probe using 3 nm spacing utilizing the Emispec vision system and STEM capability. The data set consisted of 35 spectra for a 112 nm scan line. The reduced spectra were created by extracting 12 channels in the range 204 V to 366 V for the C-K peak, 20 channels from 353 V to 635 V for the O-K peak, and 29 channels from 5231 V to 5626 V for the Cr-K peak for a total of 61 channels. Figure 5.12 shows the spectra used as the bulk phases. Processing of the original data set returned the PCs shown in Figures 5.13 and 5.14 which show the PCs are very similar to the last test and that the third PC is more distinct from the noise. The PC space coordinates of possibilities with tolerances $[0.33:0.33:-0.33]$ in Figure 5.15. No points were found if tolerances smaller than this were used. Although no direct comparison of the tolerances can be made these

are the largest minimum tolerances found thus far. The obvious difference between this and the last data sets is the number of spectra so in attempt to reproduce the tolerances in that case the data set was reduced to nine spectra by taking the end spectra and equally spaced spectra from the rest of the data set. With the reduced data set the tolerances could be reduced to $[0.1:0.1:-0.1]$ and still have results returned. The amount of information in the PCs and the significant PCs are shown in Figures 5.16 and 5.17 for the 9 spectra data set. The PCs are almost identical in both the thirty-five and nine spectra cases. It is possible that either the other sources of information present besides composition are cumulative and have a greater effect on the tolerances with larger numbers of spectra or that it is a numerical limitation in the computer code written to do the change of basis. Neither hypothesis was tested here. The answers in both cases are approximately the same after allowing for the larger tolerances in the 35 spectra data set. All answers are a variation of the spectrum shown in Figure 5.18, a spectrum of Cr. The variation occurs in the height of the Cr peak, it varies from 1400 counts to 4200 counts, which shows itself in the distribution of the phase, shown in Figure 5.19. The maximum amount varies continuously from 25% to over 100%, but within tolerances. The bulk phases show a distribution that is also sensible, Figure 5.20. By changing the peak height the amount needed to describe a spectrum changes. Having all the possibilities found consist of almost all Cr is an unexpected result but one that may have a physical answer. A line scan was taken parallel to the Cr/C interface and the distribution of C and Cr is shown in Figure 5.21. It is evident that there is a pocket of increased Cr and decreased C, which may be

indicative of unreacted Cr and it is possible that the line scan that produced this data set was taken through such a pocket of unreacted Cr [Ref. 21]. If this is indeed a legitimate answer the previous discussion on the need for a way of determining the proper peak height for the Cr is still valid.




Figure 5.12 Input bulk phase spectra




Figure 5.13 Information content of PCs




Figure 5.14 Principal components of data set




Figure 5.15 PC space coordinates of possible spectra




Figure 5.16 Principal components of nine spectra data set




Figure 5.17 Information content of PCs




Figure 5.18 Typical output spectra




Figure 5.19 Possible interface phase distributions




Figure 5.20 Possible bulk phase distributions




Figure 5.21 C/Cr profile parallel to interface

The results returned with experimental data are closely related to the results of the previous chapter. Since this is data from a physical sample there are more constraints that can be put on the data to help narrow the possibilities. Even with this, however, it seems unlikely that all possibilities but one can be discounted. If that is possible a way of identifying the proper intensity of that phase must be found. In the second data set a single answer seems to have been found. It has not been shown that this is an actual physical answer and not just an artifact although it has been pointed out that there is some physical grounds for its existence. Further study into this interface and the technique must be carried out before any definitive conclusions can be drawn.

VI. SUMMARY AND CONCLUSIONS

This attempt to develop a technique to map phases using EDS spectra by a combination of PCA and a change of basis was broken into two parts. First, modeled data was used to try to develop the technique where the correct answers were known. All of the data tested modeled an interface where there were two bulk phases of different composition and an interface phase with a composition consisting of the elements of the bulk phases. The modeled data tests were conducted using two different assumptions. To begin with all three phases were assumed known. The information sought was the distribution of the phases. Next, the interface phase was not assumed to be known and the reconstruction of its composition as well as the distribution of all three phases was attempted. A search routine was developed using MATLAB to find the interface phase. Finally, the technique was used on experimental data taken from an interface of CVDD and chromium oxide where it had been shown by Auger spectroscopy that Cr_{23}C_6 could exist as an interface phase [Ref. 19].

When all three phases were known it was found that the distribution of all the phases could be reconstructed. This was true no matter how little information the interface phase provided to the data set as a whole. Data sets were constructed that had progressively less information provided by the interface phase by decreasing the intensity level of this phase in relation to the other two. Although the distribution of the phases could always be reproduced the reconstruction of the interface phase became degraded as the amount of information contributed by the interface phase decreased. Data point

normalization, dividing each spectrum by its total intensity, was shown to alleviate this problem to some extent.

Next, the assumption of a known interface phase was removed and the distribution of all phases and the composition of the interface phase was searched for. The criteria used to identify a physically possible EDS spectrum were sufficient to identify a region of PC space where the correct answer was located but not sufficient to identify the correct answer itself. Instead the region of identified phases contained multiple combinations of the elements present in the data set. In addition, any given phase spectrum present in this region appeared multiple times with differing total intensities but with the same ratio of the elements. This changed the amount of the phase in each spectrum of the data set. There was no way to identify which of these combinations was the correct one. The modeled data did not contain any other information than what was already used to identify physical EDS spectra; neither the correct combination of the elements or the total intensity of the spectrum could be identified.

Finally, the technique was applied to an interface between CVDD and chromium oxide. Two sets of EDS spectra taken across the interface from different areas in the sample were evaluated. In the first case the range of answers included a range of C/Cr combinations. These spectra varied from pure Cr to a ratio of C to Cr that was nearly 1:1. Because this is experimental data criteria other than those already used can be applied to eliminate some of the possibilities found. Carbon and chromium only combine in certain ratios and so many of the combinations in the range of answers can be eliminated; they

correspond to combinations of the two elements that are not thought to exist. This criteria, chemically possible combinations of the elements, was not analyzed and would need to be studied before any conclusions on its effectiveness could be drawn. In the second data set only one answer was returned, Cr with little or no C. Although a physically possible reason for finding only Cr was discussed there is no further evidence that this was actually the case.

The PCA/change of basis technique for phase mapping using a series of EDS spectra was only partially successful in this study. It was found that an area in PC space where the correct answer was located could be found but that the answer could not be isolated. A further constraint on possible answers when experimental data is studied was discussed but research on its effectiveness needs to be undertaken. Without further viable constraints there is no way of determining which possibility is the correct one without prior knowledge of the answer. The statistical analysis of EDS spectra series using PCA shows some exciting possibilities but further work is needed to develop it into an effective tool to assist with EDS analysis.

LIST OF REFERENCES

1. Williams, David B. and Carter, C. Barry, *Transmission Electron Microscopy*, Plenum Press, 1996.
2. Walters, D., *Microchemical Analysis of Non-metallic Inclusions in C-Mn Steel Shielded Metal Arc Welds by Analytical Transmission Electron Microscopy*, Master's Thesis, Naval Postgraduate School, Monterey, California, June 1998.
3. Gnanadesikan, R., *Methods for Statistical Data Analysis of Multivariate Observations*, John Wiley & Sons, 1977.
4. Trebbia, Pierre and Bonnet, Noël, "EELS elemental mapping with unconventional methods I. Theoretical basis: image analysis with multivariate statistics and entropy concepts" *Ultramicroscopy*, v.34, pp. 165-178, 1990.
5. Hannequin P. and Bonnet, N., "Application of multivariate statistical analysis to energetic image series", *Optik*, v. 81, n. 1, pp. 6-12, 1988.
6. Trebbia, Pierre and Bonnet, Noël, "EELS elemental mapping with unconventional methods II. Applications to biological specimens", *Ultramicroscopy*, v. 34, pp. 179-263, 1990.
7. Bonnet, N., Simova, E., Lebonvallet, S., Kaplan, H., "New applications of multivariate statistical analysis in spectroscopy" *Ultramicroscopy*, v. 40, pp. 1-11, 1992.
8. Titchmarsh, J.M. and Dumbill, S. "Multivariate statistical analysis of FEG-STEM EDX spectra", *Journal of Microscopy*, v. 184, pp. 195-207, 1996.
9. Titchmarsh, J.M. and Dumbill, S. "Multivariate statistical analysis of FEG-STEM EDX data from radiation-induced sensitization in stainless steel", *Journal of Microscopy*, v. 188, pp. 224-236, 1997.
10. Quintana, Carmen and Bonnet Noël, "Multivariate Statistical Analysis applied to X-ray spectra and X-ray mapping of liver cell nuclei", *Scanning Microscopy*, v. 8, n. 3, pp. 563-586, 1994.
11. Brun, N., Colliex, C., Suenaga, K., Tencé, M., Bonnet N., "Recording, processing and extracting information from sequences of spatially resolved EELS spectra", *Proceedings: Microscopy and Microanalysis '97, Cleveland, Ohio*.

12. Bonnet, N., "Multivariate statistical methods for the analysis of microscope image series: applications in materials science", *Journal of Microscopy*, v. 190, pp. 2-18, 1998.
13. Saunders, Martin, Menon, Sarath, and Fox, Alan G., "Determination of interface composition variation by the application of Multivariate Statistical Analysis to Energy-Dispersive X-ray spectra and Electron Energy Loss Spectra" *Proceedings: Scandem-98, Espoo, Finland*.
14. Saunders M., Menon, E.S.K., Hashimoto, R.Y., Fox A.G., "Interface EELS analysis: Comparison of spatial difference and Multivariate Statistical Analysis (MSA) techniques", *Proceedings: International Conference of Electron Microscopy 1998*.
15. Saunders, M., Menon, E.S.K., Chisholm. D.J., Fox A.G., "Extracting chemical information from energy-dispersive X-ray spectra by Multivariate Statistical Analysis (MSA)", *Proceedings: Microscopy & Microanalysis '98, Atlanta, Ga*.
16. Saunders M., Menon, E.S.K., Fox A.G., "Using statistical methods to identify and map interface reaction phases from EDS spectra", *Proceedings: International Conference of Electron Microscopy 1998*.
17. Anton, Howard, *Elementary Linear Algebra*, 4th ed., John Wiley & Sons, Inc., 1984.
18. The MathWorks, Inc., *Statistic Toolbox User's Guide*, 1997.
19. Menon, E.S.K. and Dutta, I., (in press), "Processing and characterization of alumina thin films on chemical vapor deposited diamond substrates for producing adherent metallizations", *Journal of Materials Research*, v. 14, n.2, Feb 99.
20. Kroll, Darwin E., *Metallization of CVD Diamond Using Metal Oxide Intermediate Layers for Electronics Packaging*, Master's Thesis, Naval Postgraduate School, Monterey, California, March 1997.
21. Private communication between Dr S. Menon and the author, 8 December 1998.

INITIAL DISTRIBUTION LIST

1. Defense Technical Information Center.....2
8725 John J. Kingman Rd., STE 0944
Ft. Belvoir, Virginia 22060-6218

2. Dudley Knox Library.....2
Naval Postgraduate School
411 Dyer Rd.
Monterey, California 93943-5100

3. Naval/Mechanical Engineering, Code 34.....1
Naval Postgraduate School
700 Dyer Rd., Bldg. 245
Monterey, California 93943-5100

4. Department Chairman, Code ME/Mc.....1
Department of Mechanical Engineering
Naval Postgraduate School
700 Dyer Rd., Bldg. 245
Monterey, California 93943-5100

5. Dr. Alan G. Fox, Code ME/Fx.....2
Department of Mechanical Engineering
Naval Postgraduate School
700 Dyer Rd., Bldg. 245
Monterey, California 93943-5100

6. Dr. Martin Saunders1
Analytical Materials Physics,
The Angstrom Laboratory,
Uppsala University,
Box 534,
SE-751 21 Uppsala, Sweden

7. LT Dan Chisholm.....1
1132 Riva Ridge Blvd
Gahanna, Ohio 43230